BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

NEGOTIATED SCHEDULE - B

Developments of roads and drains at Kogilu Layout Main and Cross Roads in Ward No.05 (Jakkur)

SNo	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. G VENKATE GOWDA	
				In figures	In words
1	3383.75	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications 10km lead= 57+2.0x1.28x10 =82.60	Cum	225.93	Rupees Two Hundred Twenty Five And Paise Ninety Three Only
2	434.39	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration	Cum	5690.22	Rupees Five Thousand Six Hundred Ninety And Paise Twenty Two Only
3	24.54	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete	Cum	6031.75	Rupees Six Thousand Thirty One And Paise Seventy Five Only
4	50.94	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and	Tonne	75906.30	Rupees Seventy Five Thousand Nine Hundred Six And Paise Thirty Only
5	835.35	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering,	Cum	7420.09	Rupees Seven Thousand Four Hundred Twenty And Paise Nine Only
6	2308.50	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	2452.65	Rupees Two Thousand Four Hundred Fifty Two And Paise Sixty Five Only
7	59.52	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll	Sqm	5686.13	Rupees Five Thousand Six Hundred Eighty Six And Paise Thirteen
8	2727.00	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form	Nos	453.88	Rupees Four Hundred Fifty Three And Paise Eighty Eight Only
9	429.45	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. (I No-24.1,P No-180,KPWD SR 2018-19)	Sqm	89.00	Rupees Eighty Nine Only
10	2035.12	KSRRB M300-14. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with	Cum	67.10	Rupees Sixty Seven And Paise Ten Only
11	6308.00	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occuring during rolling	Sqm	6.68	Rupees Six And Paise Sixty Eight Only
12	834.99	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to	Cum	2093.64	Rupees Two Thousand Ninety Three And Paise Sixty Four Only

Contractor

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. G VENKATE GOWDA	
				In figures	In words
13	1252.49	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed	cum	2100.32	Rupees Two Thousand One Hundred And Paise Thirty Two Only
14	5566.60	KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means	Sqm	31.15	Rupees Thirty One And Paise Fifteen Only
15	5141.40	KSRRB 500-2. Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM complete as per	Sqm	5.56	Rupees Five And Paise Fifty Six Only
16	16708.00	KSRRB 500-7. Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications (P.No-	Sqm	13.35	Rupees Thirteen And Paise Thirty Five Only
17	535.40	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 505 of MORTH V revisionusing 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen (P.No-160,I No-21.17.6)	Cum	6724.80	Rupees Six Thousand Seven Hundred Twenty Four And Paise Eighty Only
18	428.32	Providing and laying bituminous concrete 40mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. – do – using 40-60 TPH capacity HMP with mechanical paver grading II (30-45mm) with 5.4 % of modified bituminus binder consisting of 4.97% of VG-30 bitumen (60/70 grade) and 0.43% of plastomeric thermoplastics (waste plastic)	Cum	7910.68	Rupees Seven Thousand Nine Hundred Ten And Paise Sixty Eight Only
19	240.00	KSRRB M600-1.Providing and Constructing dry lean cement concrete mix CC 1:5:10 base with OPC 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @0.58cum over a prepared sub-base, coarse and fine aggregate conforming to IS: 383-2016,aggregate cement ratio not to exceed 15:1, Aggregate gradation after blending to be as per Table 600-1,optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications. do- with OPC at 150 kg/cum and coarse aggregate 0.86cum, fine aggregate 0.58cum using Concrete Batch mix Plant at 75 cum/hr capacity with fixed form paver. (P.No-174,I No-21.1.2,KPWD SR 2018-19)	Cum	4077.15	Rupees Four Thousand Seventy Seven And Paise Fifteen Only

Contractor

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. G VENKATE GOWDA	
				In figures	In words
20	240.00	Cement concrete pavement Construction of un-reinforced plain cement concrete pavement, Thickness as per design, over a prepared sub base with 53 grade cement or any other type as per clause 1501.2.2 M30 (Grade) coarse and fine aggregate conforming to IS: 383 maximum size of coarse aggregate not exceeding 25mm , mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weight batcher as per approved mix design laid in approved fixed of 125 micron thick polythene film, wedges steel plates including levelling the form work as per drawing) Spreading the concrete with shovels rackers compacted using needle screed and plate vibrator and finished in a continuous operation including provision of contruction joints primer joint sealant curring of concrete slabs for 14 days and wateri finishing to lines and grade as per drawing and techincal specification clause 1501 with all lead lifts loading & unloading charges cost and conveyance of all materials	Cum	5468.84	Rupees Five Thousand Four Hundred Sixty Eight And Paise Eighty Four Only
21	371.20	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803(P.No-182,I No-24.15)	Sqm	477.24	Rupees Four Hundred Seventy Seven And Paise Twenty Four Only

Contractor